

To ensure sports fans aren't inconvenienced SOPA choose ITS PipeTech



Directors Message



"ITS PipeTech deliver cost effective, high quality, low risk solutions for all pipeline and culvert rehabilitation, extending the life of existing assets and infrastructure utilising environmentally responsible processes and methodologies".

Better Smarter Outcomes

Project Details



Industry: Roads

Client: Sydney Olympic Park Authority (SOPA)

Project: Remediation of the storm water drainage system serving the SOPA

The Sydney Olympic Park Complex is served by a comprehensive storm water drainage system that covers all road, parkland and building drainage needs for the site. Apart from the system serving the Newington area, the storm water drainage system is relatively new being completed during the late 1990's.

This project emerged after investigation by SOPA found that the network had suffered significant damage during construction of the park site, as well as the detection of a number of other defects that had not been identified prior to handover.

SOPA contracts involve the remediation of the storm water system which is constructed from concrete pipe ranging from 300mm to 1800mm diameter and some large box culvert sections.

SOPA was concerned that soil would infiltrate the storm water drains through the fractures that had been detected, all of which extended right through the walls of the pipe and in some cases exceeded 25mm in width. Pipe lifting holes that were not plugged and posed a risk of soil ingress. Defective cut-ins had exposed reinforcing steel that needed to be protected.

ITS PipeTech were engaged to undertake the necessary repair works to restore the structural integrity of damaged pipes and to prevent the ingress of the surrounding backfill material into the pipelines which could result in subsidence of the surface.

The scope of works included:

- Pipe cleaning;
- Re-survey of the storm water system and condition assessment reporting identifying defects;
- Submission of a repair plan to SOPA; and
- Final repair

ITS PipeTech pipeline robotics unit was used to prepare and complete full structural repairs on the defects. Three repair methodologies were used:

1. Man entry for greater than 800mm diameter pipe using cementitious and epoxy repair material
2. Robot applied epoxy injection for sealing of junctions and pipe defects
3. Point-Lining® for the repair of cracks, fragmentation, leakage, broken joints, capping off disused junctions, defective liner installations and corrosion.

ITS PipeTech have been awarded back to back contracts at SOPA over several years and have completed hundreds of repairs across the stormwater network. This ongoing work is evidence of the quality of the finished products and workmanship provided by ITS PipeTech and our range of rehabilitation solutions.



CONTACTS

www.itspipetech.com.au

NSW and Head Office:

1/13 Stanton Road, Seven Hills NSW 2147

Postal Address:

PO Box 318 Seven Hills NSW 1730

Telephone: (02) 8603 2000

Fax: (02) 8603 2001

Email: enquiries@itspipetech.com.au

Queensland Office:

2/49 Links Ave , Eagle Farm , QLD 4009

Postal Address:

PO Box 173 , Pinkenba , QLD 4008

Telephone: (07) 3630 2333

Fax: (07) 3630 2111

Email: enquiries@itspipetech.com.au

WA Office:

2/6 Dellamarta Rd, Wangara WA 6065

Telephone: (08) 9408 1648

Fax: (08) 9408 0332

Email: enquiries@itspipetech.com.au